

DACW-33-87-D-0007 Delivery Order 0006
Hop Brook Dam, Naugatuck, CT

OFFICE COPY DO NOT REMOVE

ATLANTIC TESTING LABORATORIES, LIMITED

atl

Box 29
Canton, N.Y. 13617
(315) 386-4578

Box 356
Cicero, N.Y. 13039
(315) 699-5281

June 10, 1988

U. S. Army Corps of Engineers
New England Division
424 Trapelo Road
Waltham, MA 02254-9149

Attn: Mr. Paul L'Heureux

Re: Subsurface Investigation
Hop Brook Dam, Naugatuck, CT
Contract DACW33-87-D-0007
Delivery Order No. 0006
ATL Report No. CD031-5-88

Gentlemen:

In accordance with Delivery Order No. 0006, dated 02 May 1988, attached is our final Engineering Report for the subsurface investigation performed at Hop Brook Dam, Naugatuck, Connecticut.

By copy of this letter, we are forwarding two copies to the Chief of the Geotechnical Engineering Branch.

If you have any questions or comments, please do not hesitate to call.

Respectfully submitted,

Sharon M. Jullerton for

Gregory R. Hargrave
Geologist

GRH/smf

encs.

SECTION 1
SUBSURFACE INVESTIGATION

HOPBROOK DAM
NAUGATUCK, CT

CONTRACT DACW 33-87-D-0007
CONTRACTING OFFICER:
Stanley J. Murphy, Lt. Col., CE
Deputy Division Engineer

DELIVERY ORDER NO. 0006
02 MAY 1988

PREPARED FOR: **U.S. Army Corps of Engineers**
New England Division
424 Trapelo Road
Waltham, MA 02254-9149

PREPARED BY: **Gregory R. Hargrave**
Atlantic Testing Laboratories, Limited
P. O. Box 29
Canton, NY 13617

May 31, 1988

ATL Report No. CD031-5-88

SECTION 2

TABLE OF CONTENTS

SECTION 1	Title Page
SECTION 2	Table of Contents
SECTION 3	Scope of Investigation <ul style="list-style-type: none">a. Delivery Orderb. Project Sitec. Purposed. Scope of Work
SECTION 4	Quality Control <ul style="list-style-type: none">a. General Certification Statementb. Records Takenc. Equipment Usedd. Procedures
SECTION 5	Summary of Activities and Telephone Log <ul style="list-style-type: none">Table I Summary of ActivitiesTable II Telephone Log
SECTION 6	Chain of Custody Log
SECTION 7	Safety Reports
SECTION 8	Field Inspector's Logs <ul style="list-style-type: none">a. Figure 1 - General Project Mapb. Figure 2 - Site Location Mapc. Figure 3 - Boring Location Pland. Boring Logs
SECTION 9	Other Records Taken <ul style="list-style-type: none">a. Survey Notes

SECTION 3

SCOPE OF INVESTIGATION

A. Delivery Order No. 0006

<input type="checkbox"/> CHECKED BOX APPLIES		<input checked="" type="checkbox"/> ORDER FOR SUPPLIES OR SERVICES		<input type="checkbox"/> REQUEST FOR QUOTATIONS NO. RETURN COPIES OF THIS QUOTE BY THIS IS NOT AN ORDER See DD Form 1155r		PAGE 1 OF 2	
1 CONTRACT PURCH ORDER NO DACW33-87-D-0007		2 DELIVERY ORDER NO 0006		3 DATE OF ORDER 88 MAY 02		4 REQUISITION PURCH REQUEST NO GEB 88-19	
5 ISSUED BY Dept. of the Army New England Division, Corps of Engineers 424 Trapelo Road Waltham, MA 02254-9149 Buyer/Symbol: Apidianakis/CENED-CT-C Phone: 617/647-8207				7 ADMINISTERED BY 17 Other than 61		8 DELIVERY TO <input checked="" type="checkbox"/> DEST <input type="checkbox"/> OTHER See Schedule if other	
9 CONTRACTOR QUOTE NAME AND ADDRESS Atlantic Testing Laboratories, Limited P.O. Box 29 Canton, New York 13617		10 DELIVER TO FOB POINT BY In accordance with Paragraph 6 of the Scope of Work 12 DISCOUNT TERMS NET		11 CHECK IF BUSINESS IS <input type="checkbox"/> SMALL <input type="checkbox"/> SMALL DISADVANTAGED <input type="checkbox"/> WOMEN-OWNED		13 MAIL INVOICES TO Finance & Accounting Officer at issuing office	
XXXXX Services for: U.S. Army Engineer Division, New England ATTN: Geotechnical Engineering Branch 424 Trapelo Road Waltham, Massachusetts 02254-9149		15 PAYMENT WILL BE MADE BY Finance and Accounting Officer U.S. Army Engineer Division, N.E. 424 Trapelo Road Waltham, Massachusetts 02254-9149		MARK ALL PACKAGES AND PAPERS WITH CONTRACT OR ORDER NUMBER			
16 DELIVERY <input checked="" type="checkbox"/> PURCHASE <input type="checkbox"/>		This delivery order is subject to instructions contained on this side of form only and is issued in accordance with and subject to terms and conditions of above numbered contract					
17 ACCOUNTING AND APPROPRIATION DATA/LOCAL USE 96X3123 O&M CE Civil CC1123440A00000 (MD) \$29,963.00		General Provisions of Purchase Order on DD Form 1155r EXCEPT CLAUSE NO 12 APPLIES ONLY IF THIS BOX <input type="checkbox"/> IS CHECKED, AND NO. 14 IF THIS BOX <input type="checkbox"/> IS CHECKED; special provisions 10 USC 2304(a)(3) or as specified in the schedule if within the U.S., its possessions or Puerto Rico, if otherwise under 2304(a)(5) <input type="checkbox"/> If checked, Additional General Provisions apply: Supplier shall sign "Acceptance" on DD Form 1155r and return copies					
18 Contract Line Furnish the necessary personnel and equipment to perform explorations at Hop Brook Dam, CT., in accordance with Attachment No. 1		20 QUANTITY ORDERED/ACCEPTED APPROX.		21 UNIT HR		22 UNIT PRICE \$42.00	
1.1 Geologist		140		HR		\$5,880.00	
1.3 Per Diem - Overnight Stay		16		DAY		800.00	
1.4 Mileage from Waltham, MA and return		260		MI		91.00	
2.1 Geotechnical Report		1		JOB		3,234.00	
24 UNITED STATES OF AMERICA STANLEY J. MURPHY, Lt. Col., CE, Deputy Division Engineer CONTRACTING OFFICER		25 TOTAL \$29,963.00		26 DIFFERENCES		27 INITIALS	
26 QUANTITY IN COLUMN 20 HAS BEEN: <input type="checkbox"/> INSPECTED <input type="checkbox"/> RECEIVED <input type="checkbox"/> ACCEPTED, AND CONFORMS TO THE CONTRACT EXCEPT AS NOTED		27 SHIP NO		28 PAID BY		29 AMOUNT VERIFIED CORRECT FOR	
DATE SIGNATURE OF AUTHORIZED GOVERNMENT REPRESENTATIVE		30 PAYMENT <input type="checkbox"/> COMPLETE <input type="checkbox"/> PARTIAL <input type="checkbox"/> FINAL		31 CHECK NUMBER		32 BILL OF LADING NO	
35 I certify this account is correct and proper for payment. DATE SIGNATURE AND TITLE OF CERTIFYING OFFICER		36 RECEIVED AT		37 RECEIVED BY		38 DATE RECEIVED	
39 TOTAL CONTAINERS		40 S/R ACCOUNT NUMBER		41 S/R VOUCHER NO		42 S/R VOUCHER NO	

CONTINUATION SHEET

REF NO. DOC BEING CONT'D
Delivery Order No. 0006
to DACW33-87-D-0007

PAGE 2 OF 2

NAME OF OFFEROR OR CONTRACTOR

ATLANTIC TESTING LABORATORIES, LIMITED

Contract ITEM NO	Line SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
		APPROX.			ESTIMATED
3.1	Mobilization and Demobilization	1	JOB	350.00	350.00
3.2	Mileage from and to Waltham, MA	260	MI	.35	91.00
3.4	Survey Crew and Equipment	1	DAY	560.00	560.00
3.5	Overnight Per Diem for Survey Crew	1	DAY	100.00	100.00
3.6	Data Reduction and Plotting	1	JOB	80% of Line Item 3.4	448.00
6.1	Mobilization and Demobilization	1	JOB	1,100.00	1,100.00
6.2	Mileage from/to Waltham, MA	260	MI	1.15	299.00
6.5	Standby time/on site moves	40	HR	80.00	3,200.00
13.1	0-30 Ft. Depth	32	EA	<u>14.00</u>	448.00
13.2	31-50 Ft. Depth	21	EA	<u>17.00</u>	357.00
13.3	51-100 Ft. Depth	35	EA	<u>21.00</u>	735.00
17.1	BX, NX Size	30	LF	22.00	660.00
17.2	HX and 6 Inch Size	50	LF	30.00	1,500.00
18.2	HX and 6 Inch Size	150	LF	30.00	4,500.00
22.3	NWX Size and/or NWM	35	LF	<u>55.00</u>	1,925.00
22.4	4X5½ Size, Dbl. Tube Barrel	15	LF	75.00	1,125.00
31.1	Light Lumber for Shoring Excavation	2	MBF	800.00	1,600.00
34.1	Truck with Towing Winch	12	HR	80.00	960.00

ATTACHMENT NO. 1

GEB REQUISITION 88-19-DACW 33-87-D-0007

DELIVERY ORDER NO. 6

INSPECTION AND EXPLORATION INSTRUCTIONS

PROJECT: Hop Brook Dam Explorations

SITE: Hop Brook Dam, Naugatuck, CT

PURPOSE: To determine the depth to bedrock and the composition of an abandoned railroad embankment.

1. SCOPE OF INVESTIGATIONS.

a. Four borings shall be completed at the locations shown on Attachment No. 2 according to the following schedule:

<u>BORING</u>	<u>COMPLETION DEPTH BELOW BEDROCK SURFACE</u>	<u>ESTIMATED OVERBURDEN DEPTH</u>
FD-A	15 FT	5 FT
FD-B	5 FT	92 FT
FD-C	5 FT	85 FT
FD-D	5 FT	45 FT

Locations have been staked in the field by the Government.

b. Soil sampling shall be accomplished by the SPT method. Sampling shall be continuous for FD-B and on 5-foot centers for FD-C and FD-D. There shall be no soil sampling in FD-A. It is imperative that the top of bedrock is determined and verified in all borings.

c. The Contractor shall survey the final locations and elevations of the explorations.

d. The inspector shall provide telephone reports to Mr. Paul L'Heureux, Corps of Engineers at tel. (617) 647-8597, at least once every working day. The alternate point of contact is Mr. John Hart at tel. (617) 647-8389.

e. All soil samples and cores shall be delivered by the Contractor to the Corps of Engineers, Division Materials Lab in coordination with the Laboratory Director at tel. (617) 647-8367/8392.

2. SITE CONDITIONS.

Boring FD-A is in a gorge and is accessible only by descending the riprap slope of the dam or abutments. Borings FD-B, C, and D are at the crest of an abandoned railroad embankment which may be as narrow as 6 feet in places. The composition of the embankment is unknown. It is assumed to be random fill and could contain timber trestles.

3. COORDINATION.

The Contractor shall contact Mr. Paul L'Heureux, Corps of Engineers at tel. (617) 647-8597 one week prior to the start of work. The field inspector shall give a daily telephone report on the progress of the work to Mr. L'Heureux. The Contractor shall also coordinate with Mr. Les Butler, Project Manager at Hop Brook Dam, tel. (203) 729-8840.

4. EXPLORATIONS. (see exploration plan, Attachment 2)

Borings FD-A through FD-D shall be redesignated FD-88-1 through FD-88-4 in order of their completion.

5. GOVERNMENT REVIEW.

The Government will review the draft submittal as well as the completed work. Subsequent to such review, the Contractor shall accomplish any corrections which may be directed as the result of the Government review.


6. COMPLETION SCHEDULE.

Services under this delivery order shall start on or before 2 May 1988. Duration of the field work is estimated to be seventeen days. The geotechnical report shall be submitted in draft format for review (by the Government), postmarked no later than seven calendar days after the completion of field work. Government review will take approximately ten calendar days from the receipt of draft report. The final geotechnical report shall be submitted postmarked no later than seven calendar days after the receipt of the draft report with Government comments.

7. QUALITY CONTROL.

You will be held responsible for the quality of the maps submitted and for all damages caused the Government as a result of your negligence in the performance of any services furnished under the contract.

Although submissions required by your contract are technically reviewed by the Government, it is emphasized that your work must be prosecuted using proper internal controls and review procedures. The letter of transmittal for each submission which you make shall include a certification that the submission has been subjected to your own review and coordination procedures to insure (a) completeness for each discipline commensurate with the level of effort required for that submission, (b) elimination of conflicts, errors and omissions, and (c) the overall professional and technical accuracy of the submission. Documents which are significantly deficient in any of these areas will be returned to you for correction and resubmission prior to our completing our review. Contract submission time will be extended if a resubmission of draft material is required for this reason.



HOP BROOK DAM
Niantuck, Ct
1" = 70'

approx scale 1" = 70'

Hop Brook Dam

FEA
FD 88-2

ROUTE 10

b. Project Site

The project is at the site of a flood control dam containing the waters of Hop Brook in Naugatuck, Connecticut. The investigation covered the toe of the dam and a railroad embankment immediately downstream from the dam. Boulder-sized rip-rap covered the work area at the toe of the dam, while loose cinders covered the railroad embankment. A General Project Map, Site Location Map, and Boring Location Plan are included in Section 8. A general plan of the site provided to us in the Delivery Order is in part (a) of this section.

c. Purpose

The purpose of the investigation was to recover soil and rock samples for classification and to determine the depth to bedrock. The information obtained through this study is to be used in determining the stability of the railroad embankment and the suitability of the soil contained within the railroad embankment for road construction purposes. Additional information obtained from the toe of the dam will be used for proposed construction in that general area.

d. Scope of Work

Survey, inspection, and exploration instructions, which were provided by the Army Corps of Engineers, New England Division, in Delivery Order No. 0006, are included in Section 3a. General inspection and exploration instructions were provided by the Army Corps of Engineers, New England Division, through the contract "Specifications for Various Locations in New England". Specific instructions and changes during the course of the work were given verbally during onsite visits and telephone conversations through a Corps of Engineers representative. All new instructions and changes can be found listed in Table II of Section 5.

Work under this Delivery Order consisted of locating four (4) test borings; Paul L'Heureux (USACE) assisted in locating the borings.

Drilling and sampling was performed by Atlantic Testing Laboratories' personnel using Atlantic Testing Laboratories' equipment. The test borings were advanced and sampled as indicated in the Delivery Order (Section 3a) and as outlined in the contract specifications and as amended in the conversations outlined in Table II, Section 5. Overburden sampling was performed using a 300 lb hammer driving a 2 or 5 foot split spoon sampler (2-3/8" I.D.) or 140 lb hammer driving a 2 foot split spoon sampler (1-3/8" I.D.) at the intervals designated in the Delivery Order.

A survey crew from Atlantic Testing Laboratories, Limited surveyed the final locations and elevations of the borings.

SECTION 4

QUALITY CONTROL

a. General Certification Statement

I hereby certify that the records, equipment and procedures mentioned below were used to perform the subsurface exploration described herein. I also certify that the work was performed in a professional manner and meets the requirements set forth in the Delivery Order. This report has been subject to my review and is both complete and technically accurate.

CERTIFIED June 10, 1988


Spencer F. Thew, P.E./L.S.

b. Records Taken

Pertinent drilling procedures, sampling operations, soil classifications and testing data were noted on the following forms provided for use by the Corps of Engineers:

NED 121 (Field Log of Test Boring, Summary)
NED 58 and 58a (Field Log of Test Boring)
NED 130 (Field Log of Test Boring in Rock)

A completed series of logs for each of the borings is included in Section 8 along with location maps.

Sample containers were labeled using ENG Form 1742 and were delivered to the USACE NED Materials and Water Quality Laboratory on May 27, 1988.

A summary of daily activities and a telephone log are in Tables I and II of Section 5, respectively. A chain of custody log is in Section 6. Safety meeting reports, NED Form 251, including exposure time for Atlantic Testing Laboratories', Corps of Engineers and sub-contracted personnel, are located in Section 7.

c. Equipment Used

All equipment and supplies were provided by Atlantic Testing Laboratories, Limited, with the exception of that provided by sub-contractors. A listing of pertinent equipment follows:

1. Survey Equipment

- Wild Heerburg, T-1, 6 minute Theodolite
- 25 feet, extendable, fiberglass, stadia rod

2. Drilling Equipment

- CME 850 ATV drill rig
- CME 45 drill rig mounted on skids
- HW (4") and NW (3") casing with both spin and drive shoes
- Drill rod, NX, 2 feet, 5 feet, and 10 feet lengths, used for sampling and turning 3-7/8" and 2-15/16" roller bits
- two centrifical pumps with 500 feet of black PVC pipe
- two 90 gallon tubs
- 3" O.D. by 5 foot diamond bit core barrel
- Split spoon samplers, 3" O.D. or 2-3/8" I.D. by 2 and 5 foot lengths and 2" O.D. or 1-3/8" I.D. by 2 foot length

3. Subcontracted Equipment

- International diesel tow truck, with two drums, 3/4" cables, with operator

d. Procedures

1. Survey Procedures

Atlantic Testing Laboratories, Limited surveyors were onsite May 25, 1988, to establish the as-drilled boring locations. Borings completed under this Delivery Order were referenced by occupying Station 4+60 which is the intersection of the road centerline (on the dam crest) and the outlet works (conduit) and the centerline of the road (on the dam crest) for horizontal control and the crest monument No. 4 (elevation 380.93') for vertical control.

2. Access Procedures

Boring FD88-2 (FD-A) was at the toe of the dam. This was accessed by disconnecting the guard rail cable, winching the CME 45 skid drill rig into place with its self-contained winch equipped with a 5/8" cable. A winch line from the subcontracted wrecker was used as a safety line during down slope movement. The wrecker, located on the dam crest, was used to move the rig up slope.

Borings located on the railroad embankment were accessed by the CME 850 ATV drill rig via an existing gravel trail.

3. Sampling and Drilling Procedures

Sampling techniques, as described in the contract and as modified during the work period, involved retrieving material using the Standard Penetration Test. A 3-inch O.D. or 2-3/8 inch I.D. by 2 or 5 foot long split spoon sampler was driven 2.0 or 5.0 feet and the blow counts for a 300 lb hammer falling 18 inches were recorded for every 0.5 feet advancement. Also, a 2-inch O.D. or 1-3/8-inch I.D. by 2 foot long split spoon sampler was driven 2 feet and the blow counts for a 140 lb hammer falling 30 inches were recorded for every 0.5 feet advancement. Refusal was defined as 100 blows with no penetration or bouncing refusal. The sampling interval was 5 feet or continuous as designated by the Delivery Order.

Samples were classified in the field in accordance with ASTM D-2488. Representative samples were taken from each soil sampling run and placed in one 16 oz jar with hermetically sealed lid. Rock core was placed in 5 ft long core box as specified in the contract. Sample jars were labeled using ENG Form 1742 and were delivered to the USACE NED Materials and Water Quality Laboratory on May 27, 1988. A chain of custody log was maintained to document custody of the samples between Atlantic Testing Laboratories and the Corps of Engineers.

The CME 850 and CME 45 are equipped to handle several different methods of drilling. Different techniques of advancing each hole, in conjunction with sampling, were employed which best suited the situation. These systems are generally described as follows:

- HW (4") spin casing cleaned with a 3-7/8" roller bit, used only to case the upper portion of FD88-4.
- NW (3") spin casing cleaned with a 2-15/16" roller bit, used to case the upper portion of FD88-2 (FD-A).
- HW (4") drive casing cleaned with a 3-7/8" roller bit. This method was most widely used to case borings.
- 3-7/8" roller bit was used to advance borings when casing refusal was encountered. Clear Mud was used as a drilling fluid.
- NX diamond coring, washed with water, was used to penetrate rock and obtain rock core samples.

SECTION 5
SUMMARY OF ACTIVITIES
AND
TELEPHONE LOG

TABLE I

HOP BROOK DAM, CT

CD031 - DAILY ACTIVITY LOG

<u>DATE</u>	<u>ACTIVITY</u>
May 17, 1988 Tuesday	<ul style="list-style-type: none"> - Inspector (Greg Hargrave) and 850 Drill Crew (Mike Hawkins, Paul McAloon), CME 45 Drill Crew (Randy Todd, Robin Pryce) and Scott Fox onsite 6:30 a.m. to 6:30 p.m. Paul L'Heureux onsite 10:00 a.m. to 2:00 p.m. - Held Safety Meeting - Weather: overcast, 65-70 degrees with intermittent rain throughout day - Subcontractor onsite 2 to 6 p.m. (wrecker) - At 7:15 a.m. Jim Ferral (USACE) unlocked gates so crews could access site. - Inspector and drill crews located proposed boring locations. - CME 850 drill crew set up on FD-B (FD88-1); CME 45 crew began making access available in preparation for wrecker to set up on FD-A (FD88-2). Removed guard rail cables. - Paul L'Heureux (USACE) arrived and assisted inspector in locating proposed borings. - CME 850 started drilling on FD88-1 (FD-B) at 11 a.m. - Paul L'Heureux (USACE) discussed the following with G. Hargrave (ATL): he gave approval for drill crews to work over 10 hours per day provided inspector keeps him informed on a daily basis; ATL representative to direct any questions from State of Connecticut representatives regarding drilling operations to Mr. L'Heureux (USACE). The trench in the railroad embankment made by water from drilling operations is to be backfilled from the crest to approximately 15 ft below the crest. Ten feet (10') of rock core is to be taken from FD88-1 (FD-B). The bore holes are to be backfilled with onsite soils and possibly grouted; the inspector is to check with Mr. L'Heureux later regarding grout. - Wrecker arrived at 2 p.m. to assist CME 45 drill crew in setting rig on toe of the dam. - Wrecker off site at 6 p.m. - CME 850 drillers advanced FD88-1 (FD-B) to 55 ft.

May 17, 1988
(Continued)

- Inspector talked to Les Butler (USACE) regarding project; Les Butler gave inspector keys to the gates so drillers could begin work in the morning before USACE employees were onsite.
- 16 hours standby for bore hole moves.

May 18, 1988
Wednesday

- Inspector and drill crew onsite 6:30 a.m. to 6:30 p.m.
- Weather overcast, 70 degrees, intermittent light rain throughout day.
- CME 45 drill crew continued moving drill rig into position at toe of dam and started drilling FD88-2 (FD-A).
- CME 850 drill crew advanced FD88-1 (FD-A) to 109.5'.
- CME 45 drill crew advanced FD88-2 (FD-A) to 17.5'.
- Four (4) hours standby time for bore hole move.

May 19, 1988
Thursday

- Inspector and drillers onsite 6:30 a.m. to 6:00 p.m.
- Weather overcast, raining intermittently, 70 degrees.
- Subcontractor onsite 2:30 p.m. to 4:15 p.m.
- CME 850 drill crew grouted FD88-1 (FG-B) and pulled casing. CME 850 was then set up on FD88-3 (FD-C) and started drilling operations.
- CME 45 drill crew continued advancing FD88-2 (FD-A) to 31.5' with bedrock at 12.5'. Although 15' of bedrock was requested, 20' was taken due to gravel at the beginning of run 4 suggesting bedrock occurred at 16.5' not 12.5'. Later it was established the casing was not properly seated in the bedrock at 12.5' which allowed gravel to leak into the hole. At completion of FD88-2 (FD-A) the crew secured the CME 45 for the trip up the dam face. The tow truck pulled the CME 45 up the face of the dam.
- Hole FD88-3 (FD-C) was advanced to 56.2'.
- 6.5 hours standby for bore hole moves.

May 20, 1988
Friday

- Inspector and drillers onsite 6:30 a.m. to 11:00 a.m.
- Weather overcast, raining intermittently, 70 degrees.
- CME 850 drill crew advanced hole FD88-3 (FD-C) to 75.3'.
- Drill crew picked up the site and departed.
- Les Butler (USACE) gave the ATL crew permission to store soil samples, rock core and various other equipment at the Corps office garage. Also gave permission to ATL crew to park Mac truck and trailer next to Corps office.

May 23, 1988
Monday

- Inspector and drillers onsite 1:30 to 7:30 p.m.
- Weather hot, humid and partly cloudy.
- Vandals struck over the weekend; they threw the mud tubs down the railroad embankment, pulled circuit breakers out of drill rig and pulled gin line out of tower.
- Drill crew pulled casing out of FD88-3 (FD-C) and moved to FD88-4 (FD-B) which was advanced to 28'.
- One hour standby for bore hole move.

May 24, 1988
Tuesday

- Inspector and drill crews onsite 6:30 a.m. to 3:30 p.m.
- Tony Firicano (USACE) onsite 10 a.m. to noon.
- Weather hot, humid, partly cloudy.
- Held safety meeting.
- Drillers continued to advance FD88-4 (FD-D).
- Tony Firicano (USACE) arrived onsite at 10 a.m. to watch drilling operations.
- Drillers terminated hole at 43.5' after taking 10' of rock core.
- G. Hargrave (ATL) asked T. Fericonno (USACE) if there was anything more he wanted done (i.e., more rock core from FD88-4 (FD-D) or more holes); he said no.
- The inspector organized the rock core in core boxes.
- One hour standby, bore hole move.

May 25, 1988
Wednesday

- Survey crew and inspector onsite 9 a.m. to noon.
- Weather rainy, 60 degrees.
- Geotechnical inspector assisted survey crew in locating borings to be surveyed.
- Survey crew completed survey of boring locations and elevations.
- Geotechnical inspector returned key to gates to USACE representative at Hop Brook office.
- Geotechnical inspector removed rock core boxes from USACE garage and made final inspection of site.

TABLE II

HOP BROOK DAM, CT.

CD031 - DAILY TELEPHONE LOG

<u>Date</u>	<u>Conversation</u>
March 18, 1988 Friday	<p>- 9 a.m. - Ron DeFilippo (USACE) to Spencer Thew (ATL)</p> <p>Railroad Embankment: 3 holes - 1 - 92' overburden & 5' bedrock 1 - 85' overburden & 5' bedrock 1 - 45' overburden & 5' bedrock</p> <p>R. DeFilippo (USACE) estimated 12 days of drilling and is preparing the Delivery Order.</p>
May 12, 1988 Thursday	<p>- 10:45 a.m. - Ron DeFilippo (USACE) to Spencer Thew (ATL)</p> <p>R. DeFilippo (USACE) indicated that the Delivery Order No. 6 for Hop Brook Dam was in the mail. S. Thew (ATL) told R. DeFilippo (USACE) that he had received it on or about Tuesday, May 10 and that he is currently scheduling the project and would return a call to him to tell him the specific schedule.</p> <p>- 3:30 p.m. - Spencer Thew (ATL) to Ron DeFilippo (USACE)</p> <p>S. Thew (ATL) notified R. DeFilippo (USACE) that mobilization would be on Monday, May 16, 1988, and drilling would start at 8 a.m. to 10 a.m. on Tuesday, May 17. ATL will be mobilizing two drill rigs - CME 850 to do the three deep borings at the top of the dam and a second rig to do one boring at toe of the dam.</p> <p>R. DeFilippo (USACE) authorized two mobilization charges during the conversation.</p>
May 17, 1988 Tuesday	<p>- 9 a.m. - Greg Hargrave (ATL) to USACE office in Waltham, MA</p> <p>Tried to contact Paul L'Heureux (USACE) regarding job start-up. Tony Ferriconno (USACE) said Paul L'Heureux (USACE) was on his way to the job site.</p> <p>- 9:45 a.m. - Greg Hargrave (ATL) to Tom Pahler (ATL)</p> <p>Greg Hargrave gave T. Pahler job up-date.</p>

May 18, 1988
Wednesday

- 4 p.m. - G. Hargrave (ATL) to Paul L'Heureux (USACE)

Yuri Yatsevitch (USACE) answered phone and then phone connection was broken. G. Hargrave (ATL) tried repeatedly until 4:30 p.m. to contact USACE office but no one answered.

- 4:30 p.m. - G. Hargrave (ATL) to ATL main office
G. Hargrave (ATL) gave T. Pahler (ATL) job update.

May 19, 1988
Thursday

- 8:30 a.m. - G. Hargrave (ATL) to John Hart (USACE)

G. Hargrave (ATL) gave progress report and previous two days time to J. Hart (USACE). J. Hart (USACE) wants drillers to use a 2" spoon to improve sample recovery. Once the holes are done, they do not have to be grouted but are to be backfilled with onsite soils.

- 10:45 a.m. - G. Hargrave (ATL) to Tony Firicano (USACE)

G. Hargrave (ATL) gave T. Ferriconno (USACE) job up-date; also asked if a 300 lb hammer could be used in lieu of a 140 lb hammer for sampling. He said no - use the 140 lb hammer with the 2" O.D. spoon.

May 20, 1988
Friday

- 8 a.m. - G. Hargrave (ATL) to ATL Main office

G. Hargrave asked J. Scott (ATL) to ask T. Pahler (ATL) if there was anything to bring home; T. Pahler said no.

- 8:15 a.m. - G. Hargrave (ATL) to Paul L'Heureux (USACE)

G. Hargrave (ATL) gave P. L'Heureux (USACE) job up-date and told him why 20' of bedrock was taken on FD88-2 (FD-A); also gave him names of the drill crew.

- 9:45 a.m. - G. Hargrave (ATL) to J. Hart (USACE)

G. Hargrave (ATL) gave J. Hart (USACE) a job update and previous days' time then told him drillers have advanced approximately 6' into bedrock, penetrating one foot with the roller bit and 5' with the diamond core bit. J. Hart (USACE) requested another 5' run.

- 10 a.m. - G. Hargrave (ATL) to John Hart (USACE)

G. Hargrave (ATL) explained the risks involved in obtaining another 5' run (i.e., hole was starting to collapse making coring difficult). J. Hart agreed that the hole had been advanced far enough but on the next hole, 10' of bedrock is to be obtained.

May 23, 1988
Monday

- 8:30 a.m. - G. Hargrave (ATL) to USACE (Hop Brook Dam Office)

G. Hargrave (ATL) told USACE representative at dam that drill crew would be onsite at approximately 2 p.m.

- 8:35 a.m. - G. Hargrave (ATL) to Tony Ferriconno (USACE)

G. Hargrave (ATL) told T. Ferriconno (USACE) that drill crew would be on-site at approximately 2 p.m. He told G. Hargrave (ATL) that he would be onsite tomorrow.

May 24, 1988
Tuesday

- 8:30 a.m. - G. Hargrave (ATL) to Tom Pahler (ATL), Canton

T. Pahler (ATL) told G. Hargrave (ATL) that survey crew will be onsite today or tomorrow. G. Hargrave (ATL) is to check back later in day.

- 1:15 p.m. - G. Hargrave (ATL) to T. Pahler (ATL) at Canton

T. Pahler told G. Hargrave that the survey crew would be on-site tomorrow.

SECTION 6

CHAIN OF CUSTODY LOG



atl

ATLANTIC TESTING LABORATORIES, Limited

CHAIN OF CUSTODY LOG

PROJECT: Hop Brook Dam, CT
D.O. 0006

ITEMS: Tubes _____
Bottles _____
Jar Samples (4 boxes) _____
Core Boxes 5 _____
Sampling Logs 4 _____

<u>Date & Time Received</u>	<u>Date & Time Transferred</u>	<u>Comments</u>	<u>Custodian</u>
as sampled	5/25/88 (1:30 pm)		G. Hargrave (ATL)
5/25/88 (1:30 pm)	5/27/88 6:45 AM		A. Brown (ATL)
5/27/88 6:45 AM	5/27/88 1:10		J. KING (ATL)
5/27/88 1:10			H. Boedean

SECTION 7

SAFETY REPORTS

WEEKLY SAFETY MEETING

NEDSO

Date held 5-17-88THRU: Area Engineer, New England AreaTime 6:00 - 6:15

TO: Safety Office, NED

Report No. 1

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 0006 Contractor Atlantic Testing Laboratories, Ltd.Conducted By Greg Hargrove All personnel present (Contr) -6-
(Sub) -0-
(Govt) -0-

Subjects discussed (Note, delete, or add):

EM 385-1-1, Section: _____

Accident Prevention Plan

- ✓ Individual Protective Equipment - gloves, safety shoes, and hard hats
- ✓ Prevention of Falls - be careful around steep slopes
- ✓ Back Injury, Safe Lifting Techniques -
- Fire Prevention -
- ✓ Sanitation, First Aid, Waste Disposal - keep work area neat
- Tripping Hazards - trash, hose, nails in lumber -
- Staging, Ladders, Concrete Forms, Safety Nets -
- Hand Tools, Portable Power Tools, Woodworking Machinery -
- ✓ Equipment Inspection & Maintenance (Zero Defects) -
- ✓ Hoisting Equipment -
- ✓ Ropes, Hooks, Chains and Slings -
- Electrical Grounding, Temporary Wiring, GFCI -
- Lockouts for safe clearance procedures - electrical, pressure, moving parts -
- Welding, Cutting -
- Excavations -
- ✓ Loose Rock and Steep Slopes -
- Explosives -
- Water Safety -
- Toxic materials - hazards, MSDS, respiratory, ventilation -
- Other -

2. Forwarded.

Prepared by Greg Hargrove Title GeologistSignature Greg P. Hargrove
Resident Engineer

CP: EXPOSURE HOURS:

Work Date: 5/23, 5/24, 5/25Non-work Date: 5/22, 5/26, 5/27, 5/28NED FL 251
APR 82

Man Hours:

Contr: 179.25Subcontr: 5.75Govt: 4TOTAL: 189

WEEKLY SAFETY MEETING

NEDSO

Date held 5-24-88THRU: Area Engineer, New England AreaTime 6:00 - 6:15

TO: Safety Office, NED

Report No. 2

1. Weekly safety meeting was held this date for the following personnel:

Contract No. /D.O.No. 0006 Contractor Atlantic Testing Laboratories, Ltd.Conducted By Greg Hargrave All personnel present (Contr) - 3 -(Sub) - 0 -(Govt) - 0 -

Subjects discussed (Note, delete, or add):

EM 385-1-1, Section: _____

Accident Prevention Plan

✓ Individual Protective Equipment - Hard hat, gloves, safety shoes

✓ Prevention of Falls - watch steep slopes

✓ Back Injury, Safe Lifting Techniques - use proper equipment

Fire Prevention -

✓ Sanitation, First Aid, Waste Disposal - keep work area neat

Tripping Hazards - trash, hose, nails in lumber - "

Staging, Ladders, Concrete Forms, Safety Nets -

Hand Tools, Portable Power Tools, Woodworking Machinery -

✓ Equipment Inspection & Maintenance (Zero Defects) -

✓ Hoisting Equipment - Zero defects

Ropes, Hooks, Chains and Slings - " "

Electrical Grounding, Temporary Wiring, GFCI -

Lockouts for safe clearance procedures - electrical, pressure, moving parts -

Welding, Cutting -

Excavations -

✓ Loose Rock and Steep Slopes -

Explosives -

Water Safety -

Toxic materials - hazards, MSDS, respiratory, ventilation -

Other -

Prepared by Greg Hargrave Title Geologist

2. Forwarded.

CP: EXPOSURE HOURS:

Work Date: 5/17, 5/18, 5/19, 5/20Non-work Date: 5/16, 5/21NED FL 251
APP 82

Signature

Greg Hargrave
Resident Engineer

Man Hours:


Contr: 69.0Subcontr: 0Govt: 2.0TOTAL: 71.0

SECTION 8

FIELD INSPECTOR'S LOGS

a. Figure 1 – General Project Map

GENERAL PROJECT MAP



PROJECT No CD031


SCALE: 1" = 7 miles

CONNECTICUT

b. Figure 2 - Site Location Map

FIGURE 2

SITE LOCATION MAP




PROJECT No CD031


SCALE: 1:24,000

U.S.G.S. QUAD: WATERBURY, CONN.

c. Figure 3 – Boring Location Plan



LOCATION MAP
SCALE 1"=2000' (APPROX)



● New Piezometer

Piezometer	Station	Offset from to Riser	Elev-Top of Riser	Elev-Bottom Piez. Tip
FD88-8	5+20.0	11.3' b/s	383.23'	284.4'
FD88-9	5+21.2	51.5' u/s	368.45'	290.5'
FD88-10	4+59.8	81.4' u/s	356.44'	296.9'
FD88-11	3+81.2	125.1' u/s	342.36'	286.5'
FD88-12	5+09.9	191.7' b/s	315.80'	274.7'
FD88-13	5+21.8	103.5' b/s	346.51'	279.5'
FD88-14	3+97.4	162.0' b/s	324.65'	272.6'



GRAPHIC SCALES

DES. BY		DR. BY	CK. BY	SUBMITTED:	
CHIEF:		SECTION		APPROVAL RECOMMENDED:	
CHIEF:		REVIEWED:		PROJECT MANAGER:	
APPROVAL RECOMMENDED:		APPROVED		DATE	
CHIEF, PROJECT MNGT. BRANCH		CHIEF, ENGINEERING DIVISION		SCALE	
				SPEC. NO.	
				DRAWING NUMBER	
SHEET					

d. Boring Logs

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Hop Brook C.T. PROJECT NO. DO 0006
 Hole No. FD88-1 Diam. (Casing) HW (4") Page 1 of Pages
 (FD-8)
 Co-ordinates: N E Boring Started May 17, 1988
 Drilled by M. Hawkins + P. Mc Aloon Boring Completed May 18, 1988
 Report Submitted May 31, 1988

Purpose of Exploration To determine subsurface soil condition and depth

Elevation Top of Hole 370.3 M.S.L.
 Total Overburden Drilled 99.9 Feet
 Elevation Top of Rock 270.4 M.S.L.
 Elevation Bottom of Hole 260.8 M.S.L.
 Total Rock Drilled 19.5 Feet
 Total Depth of Hole 109.5 Feet
 Core Recovered 83.9 %
 Core Recovered 16.1 Ft.; NX Diam. 2 1/8 In.
 Soil Samples 3 In. Diam. 18 No.
 Soil Samples In. Diam. No.

Casing Left in Place 0 Feet

Water Table Depth

Depth		Method of Drilling and Type of Bit Used
From	To	
0	90'	HW casing advanced with 300 lb hammer
0	90'	continuous soil sampling
90.0	90.3	3 7/8" O.D. roller bit
90.3	109.5	NXM DIAMOND CORE

INDEX	
Ground Water	Back of Page <u> </u>
Boring Location Sketch	Back of Page <u> </u>
Overburden Record	Page <u> </u>
Rock Drilling	Page <u>8</u>
	Page <u> </u>
	Page <u> </u>
	Page <u> </u>

Prepared by Gregory R. Hargrave
 Field Data

Lab. Data

Submitted by Atlantic Testing Laboratories, Limited

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Hop Brook CT Page 2 of 2 Pages
Boring No. FD88-1 Desig. FD B Diam. (Casing) 4" (H.W.)
Co-ordinates: N E

FIELD LOG OF TEST BORING

Elevation Top of Boring 370.9 M.S.L. Hammer Wt. 300lbs Boring Started 5-17-88
Total Overburden Drilled 99.9 Feet Hammer Drop 18.0 Boring Completed 5-18-88
Elevation Top of Rock 270.4 M.S.L. Casing Left 0
Total Rock Drilled 19.2 Feet | Subsurface Water Data | | Page
Elevation Bottom of Boring 260.8 M.S.L. Obs. Well NA
Total Depth of Boring 109.5 Feet Drilled By M. Hawkins + P. McAloon
Core Recovered 83.9 % No. Boxes 1 Mfg. Des. Drill CME 850
Core Recovered 19.2 Ft : UX Diam. 2 1/2 In. Inspected By: Greg Hargrave
Soil Samples 3 In. Diam. 18 No. Classification By: Greg Hargrave
Soil Samples In. Diam. No. Classification By:

DEPTH		CORE/SAMPLE		BLOWS PER FOOT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS	
	1" 2'	NO.	SIZE	DEPTH RANGE			CORE RECOVERY
0				Rec	1 1 2 2 1 5 3 20 2 1	Sampled using 3" O.D x 5' split spoon sampler using a 300 lbs hammer Advanced HW casing to 5' using a 300 lbs hammer Cleaned casing used 3 7/8" O.D. roller bit and water	Poorly graded sand with gravel (SP) Black sand and gravel sized cinders trace amounts of wood
5'		S-1	3"	10%			
		S-2A			WOH ↓ 1	Sampled from 5' to 10'	Similar Soils (SP)
			3"	20%	↓ 1 ↓ 1 ↓ 1 ↓	Advanced casing to 10' Cleaned casing to 10'	
		S-2B					Silty Sand (SM) About 60% sand, 30% fines, and 10% gravel, moist, non plastic)
10'							
GENERAL REMARKS: WOH Denotes weight of hammer WOR Denotes weight of rod							

GENERAL REMARKS:

WOH Denotes weight of hammer

WOR Denotes weight of rod

Site				Boring No.				Page <u>3</u>	
Hop Brook CT				FD 88-1 (FD-B)				of <u> </u>	
DEPTH		CORE/SAMPLE		BLOWS PER FT.		6" SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS	
	1" 2"	NO.	SIZE	DEPTH RANGE	CORE RECOVERY				
10'				Rec.	1	Sampled from 10' to 15'		Similar Soils (SM)	
					1	Advanced casing to 15'			
					1	Cleaned casing to 15'			
					1				
		S-3	3"	40%	1				
					1				
					2				
					1				
					1				
					1				
15'					1				
					6	Sampled from 15' to 20'		Similar Soils (SM)	
					1	Advanced casing to 20'			
					1	Cleaned casing to 20'			
					1				
		S-4	3"	20%	1				
					1				
					1				
					1				
					2				
					1				
20'					9	Sampled from 20' to 25'		Silty sand with gravel (SM) about 45% cm f sand 30% silt and 25% gravel (moist, non-plastic)	
					2	Advanced casing to 25'			
					2	Cleaned casing to 25'			
					1				
		S-5	3"	40%	2				
					3				
					2				
					2				
					1				
					1				
25'					1	Sampled from 25' to 30'		Well graded gravel (BW) about 95% brown cm f GRAVEL, 45% silt, 45% sand (saturated, non-plastic)	
					1	Advanced casing to 30'			
					1	Cleaned casing to 30'			
					1				
		S-6	3"	10%	1				
					1				
					1				
					1				
					1				
					1				

Hop Brook, CT

FD 88-1 (FD-B)

DEPTH	CORE/SAMPLE		BLOWS PER FT.	6' SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	REMARKS		
30'	S-6	3"	rec WOH ↓ 1		
35'	S-7	3"	20% ↓ 1 ↓ 1 ↓ 1	Sampled from 30' to 35' Advanced casing to 35' Cleaned casing to 35'	Silty sand (SM) about 65% brown cmf sand, 25% silt. and 10% cmf gravel
40'	S-8	3"	0% WOH ↓	Sampled from 35' to 40' Advanced casing to 40' Cleaned casing to 40'	
	S-9	3"	20% WOH ↓ 1 ↓ 1 ↓ 2 ↓ 2	Sampled from 40' to 45' Advanced casing to 45' Cleaned casing to 45'	Poorly graded sand (SP) about 90% brown cmf sand, 5% silt and 5% mf gravel

• Hop Brook CT

FD 88-1

FD-B

DEPTH		CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
1' 2'	NO.	SIZE	RECOVERY	REMARKS		
45'				Rec	/	
					/	
					/	
					2	
					1	
		5-10	3"	10%	1	
					1	
					1	
					1	
					1	
50'					1	
					1	
					WOH	
					1	
					1	
					1	
		5-11	3"	10%	1	
					1	
					1	
					1	
					2	
					2	
55'						
					END OF EXPLORATION 5/17/88	
					EXPLORATION CONTINUED 5/18/88	
					WOH	
					1	
					1	
					1	
					1	
		5-12	3"	20%	1	
					1	
					1	
					1	
					1	
60'					1	
					1	

A (Test)

Boring No. FD 88-1

FD 88-1 (FD-B)

(Test)

Boring No. FP 88-1

DEPTH	CORE/SAMPLE		BLOWS PER FOOT	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	RECOVERY		
80'		3"	Rec		
85'	S-17	3"	20%	<p>Sampled from 80' to 85'</p> <p>Advanced casing to 85'</p> <p>Cleaned casing to 85'</p>	Soils similar to sample #13: (coarser sand)
90'	S-18	3"	30%	<p>Sampled from 85' to 90'</p> <p>Advanced casing to 90'</p> <p>Cleaned casing to 90'</p>	Wood
90.3'				<p>Attempted sampling at 90'</p> <p>bouncing refusal</p> <p>Advanced 3 7/8" O.D. roller bit to 90.3</p>	Grey Gneiss
95'	R-1	NX	95%	<p>Advanced NX DIAMOND CORE from 90.3' to 95.3</p>	<p>95% Recovery</p> <p>RQD = 62%</p> <p>6 pieces, some fragments</p> <p>Note - 3 mortar layers of $\approx 1"$ thickness from 91.9' to 92.7'</p>

FD 88-1 (FD-41)

Boring No. FD 88-1.

FIELD LOG OF TEST BORING IN ROCK

SITE Hop Brook Dam, CT

ROLE NO. FD 88-1 (FE B)

PAGE 9

DATE	DEPTH PT.		RUN PT.	RUN REC' V' Y PT.	REC' V' Y %	DRILLING BEHAVIOR			ACTUAL DRILLING TIME	BIT NO. SIZE AND TYPE	ADDITIONAL REMARKS
	FROM	TO				PEED	WATER	REASON FOR POLL			
5/18/88	90.3	95.3	5'	4.75	95%	Medium	No Return	5' run	30 min	NXM	Run 1
5/18/88	95.3	100.3	5'	2.25	45%	Medium	No Return	5' run	35 min	NXM	Run 2
5/18/88	100.3	105.3	5'	4.1	82%	Medium	No Return	5' run	25 min	NXM	Run 3
5/18/88	105.3	109.5	4.2'	5'	100%	Medium	No Return	4.2' run	25 min	NXM	Run 4

TOTAL BED ROCK DRILLED 19.2 FEET

TOTAL BED ROCK RECOVERED 16.1 FEET

BED ROCK RECOVERY 83.9 PERCENT

DRILLER Mike Hawkin + Paul McElloin

INSPECTOR Grog Hargrave

NED FORM 130
DEC 63

REPLACES EDITION OF APR 63 WHICH MAY BE USED UNTIL EXHAUSTED

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

PROJECT NO. D.O. 0006

Site Hop Brook Dam CT

Page 1 of Pages

Hole No. FD88-2 Diam. (Casing) NW (3")
(FD-A)

Boring Started May 18, 1988

Co-ordinates: N E

Boring Completed May 19, 1988

Drilled by Randy Todd and Robin Price

Report Submitted May 31, 1988

Purpose of Exploration To determine bedrock depth

Elevation Top of Hole 280.5 M.S.L.

Casing Left in Place ☐ Feet

Total Overburden Drilled 12.5 Feet

Elevation Top of Rock 268 M.S.L.

Elevation Bottom of Hole 249 M.S.L.

Total Rock Drilled 31.5 Feet

Total Depth of Hole 31.5 Feet

Core Recovered 85 %

Core Recovered 24.7 Ft.; NX Diam. 2 1/8 In.

Soil Samples In. Diam. No.

Soil Samples In. Diam. No.

Water Table Depth

Depth		Method of Drilling and Type of Bit Used	INDEX
From	To		
0	12.5	NW (3" I.D.) spun casing	Ground Water <u> </u> Back of Page <u> </u>
0	31.5	NX DIAMOND CORE	Boring Location Sketch <u> </u> Back of Page <u> </u>
			Overburden Record <u> </u> Page <u> </u>
			Rock Drilling <u> </u> Page <u> </u>
			<u> </u> Page <u> </u>
			<u> </u> Page <u> </u>
			<u> </u> Page <u> </u>

Prepared by Greg Hargrave Field Data

Lab. Data

Submitted by Atlantic Testing Laboratories Limited

FIELD LOG OF TEST BORING

Co-ordinates: N E

Elevation Top of Boring 280.5 M.S.L. Hammer Wt. N/A Boring Started 5-18-88
Total Overburden Drilled 12.5 Feet Hammer Drop N/A Boring Completed 5-19-88
Elevation Top of Rock 268 M.S.L. Casing Left 0
Total Rock Drilled 29 Feet | Subsurface Water Data: | Page
Elevation Bottom of Boring 249 M.S.L. Obs. Well
Total Depth of Boring 31.5 Feet Drilled By Todd + Price
Core Recovered 85 % No. Boxes 2 Mfg. Des. Drill CME 45
Core Recovered 24.7 Ft : NX Diam. 2 1/2 In. Inspected By: Hargrave
Soil Samples In. Diam. No. Classification By: Hargrave
Soil Samples In. Diam. No. Classification By:

DEPTH	CORE/SAMPLE		BLOWS PER FT.	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE	DEPTH RANGE		
1.0'	R-1	NX	Rec 100%	NX DIAMOND CORE with water from 0.0' to 1.0'	Boulders
2.5'					
6.5'	R-2	NX	60%	NX DIAMOND CORE with water from 2.5' to 6.5' Void from 4' to 5.5' Advanced NW casing to 6.5' Clean casing to 6.5' using 2 15/16" O.D. roller bit and water	
	R-3	NX	53%	NX DIAMOND CORE with water from 6.5' to 11.5' void - 10'-11.5' Advanced roller bit to to sound rock at 12.5'	

GENERAL REMARKS:

Site				Boring No.		Page <u>3</u> of <u> </u>	
Hop Brook Dam LT				FD 88-2 (FDA)			
DEPTH		CORE/SAMPLE		BLOWS PER FT.		SAMPLING AND CORING OPERATIONS	
1' 2'		NO	SIZE	RECOVERY	RECOVERY	CLASSIFICATION OF MATERIALS	
				Rec.		Advanced casing to 12.5' cleaned casing to 12.5'	
12.5'							
						NX DIAMOND CORE from 12.5 to 17.5'	
		R-4	NX	76%		Bedrock Grey Gneiss 76% Recovery 56% RQD	
17.5'							
						END OF EXPLORATION 5/18/88 EXPLORATION CONTINUED 5/19/88	
						NX DIAMOND CORE from 17.5' to 21.5'	
		R-5	NX	100%		Note: Run 5 picked up: segment of run 4 that was left in hole	
21.5'							
						NX DIAMOND CORE from 21.5' to 26.5'	
		R-6	NX	100%		Similar Rock 100% Recovery 100% RQD	
26.5'							

(Test)

Boring No. FD 88-2

FD 88-2 (ED-M)

Boring No. FD 88-2

FIELD LOG OF TEST BORING IN ROCK

SITE Hop Brook Dam, CT

ROLE NO. FD 88-2 (FD-H)

PAGE 5

[illegible]

TOTAL ~~RED~~ ROCK DRILLED 29. FEET

TOTAL ~~REV~~ ROCK RECOVERED 24.7 FEET

DRILLER M. Hawkins + P. McAloon

BED ROCK RECOVERY 85 PERCENT

INSPECTOR Greg Hargrave

NED FORM 130
DEC 6)

REPLACES EDITION OF APR 63 WHICH MAY BE USED UNTIL EXHAUSTED

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

PROJECT NO. D.O.0006

Site Hop Brook Dam, CT

Page 1 of Pages

Hole No. FD88-3 Diam. (Casing) HW (4")
(FD-C)

Boring Started May 19, 1988

Co-ordinates: N E

Boring Completed May 20, 1988

Drilled by Mike Hawkins & Paul McAloon

Report Submitted May 31, 1988

Purpose of Exploration To determine the subsurface soil conditions and depth

Elevation Top of Hole 370.5 M.S.L.

Casing Left in Place 0 Feet

Total Overburden Drilled 69.3 Feet

Elevation Top of Rock 301.2 M.S.L.

Elevation Bottom of Hole 295.2 M.S.L.

Total Rock Drilled 20.2 Feet

Total Depth of Hole 75.3 Feet

Core Recovered 64 %

Core Recovered 13 Ft.: NX Diam. 2 1/8 In.

Soil Samples 2 3/8 In. Diam. 3 No.

Soil Samples 1 3/8 In. Diam. 6 No.

Water Table Depth

Depth		Method of Drilling and Type of Bit Used
From	To	
0	62'	Split spoon soil sampling @ 5' intervals
41	70.3	3 7/8" roller bit advanced using "clean mud"
41	56.2	NX DIAMOND CORE
70.3	75.3	NX DIAMOND CORE

INDEX

Ground Water Back of Page
Boring Location Sketch Back of Page
Overburden Record Page
Rock Drilling Page
 Page
 Page
 Page

Prepared by Greg Hargrave
Field Data

Lab. Data

Submitted by Atlantic Testing Laboratories, Limited

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Hop Brook Dam, CT Page 1 of 1 Pages

Boring No. FD 88-3 Desig. FD-C Diam. (Casing)

FIELD LOG OF TEST BORING

Co-ordinates: N E

Elevation Top of Boring M.S.L. Hammer Wt. 300/140 Boring Started Mar. 19, 1988
Total Overburden Drilled 69.3 Feet Hammer Drop 18/30"
Elevation Top of Rock M.S.L. Casing Left 0 Boring Completed Mar. 20, 1988
Total Rock Drilled 20.2 Feet | Subsurface Water Data: | Page
Elevation Bottom of Boring M.S.L. } Obs. Well NA
Total Depth of Boring 75.3 Feet } Drilled By Mike Hawkins & Scott Fox
Core Recovered % No. Boxes Mfg. Des. Drill CME 850
Core Recovered Ft : Diam. In. Inspected By: G. Hargrave
Soil Samples 2 3/8 In. Diam. 3 No. Classification By: G. Hargrave
Soil Samples 1 3/8 In. Diam. 6 No. Classification By:

DEPTH		CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	1" 2'	NO.	SIZE	DEPTH RANGE		
2'		S-1	3"	100%	Rec / / / / Sampled from 0 to 2' using a 3" O.D. sampling spoon advanced with a 300lb. hammer Advanced casing to 5' cleaned casing to 5' using a 3 7/8" O.D. roller bit and water	Cinders
5'						
7'		S-2	3"	100%	/ 2 2 / Sampled from 5' to 7' Advanced casing to 10' Cleaned casing to 10'	Silty sand (SM) About 50% medium fine sand, 40% silt and 5% gravel (moist, non-plastic)
GENERAL REMARKS:						

DEPTH		CORE/SAMPLE				BLOWS PER FT. CORRECTION	3" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	1:2	NO.	SIZE	DEPTH CORRECTION	REMARKS			
10'		S-3	2"	Rec	/	/	Sampled using a 2" spoon advanced with a 300 lbs hammer Note: recovered sample obtained using 3" spoon from 10' to 12'	Similar Soil (SM)
12'								
				-	-	-	advanced casing to 15'	Similar Soil (SM)
				-	-	-	cleaned casing to 15'	
				-	-	-		
15'				-	-	-		
		S-4	2"		/	/	Sampled from 15' to 17' using a 2" spoon and a 300 lbs hammer	Similar Soil (SM)
17'								
							Advanced casing to 20'	Similar Soil (SM)
							Cleaned casing to 20'	
20'								
		S-5	3"		6	5	Sampled from 20' to 22' using a 3" spoon advanced with a 300 lbs hammer	Similar Soil (SM)
22'								
							Advanced casing to 25'	Poorly graded sand (SP) About 90% coarse sand; 5% medium-fine gravel; 5% silt (saturated, non-plastic)
							Cleaned casing to 25'	
25'								
		S-6	2"		42	15	Sampled from 25' to 27' using a 3" spoon advanced with a 140 lbs hammer Advanced casing to 30' Cleaned casing to 30'	Poorly graded sand (SP) About 90% coarse sand; 5% medium-fine gravel; 5% silt (saturated, non-plastic)
27'								

(Test)

Boring No. FD 88-3

DEPTH	CORE/SAMPLE		BLOWS PER FT. CORE RECOVERY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	1" 2'	NO.	SIZE		
30'					
32'		S-7	2"	10%	60 18 11 11 Sampled from 30' to 32' - Advanced casing to 35' cleaned casing to 35'
35'					
37'		S-8	2"	30%	9 7 6 10 Sampled from 35' to 37' Advanced casing to 40' Cleaned casing to 40'
40'					Note: encounter difficult drilling from \approx 37' to 40'
41'					Advanced 3 $\frac{7}{8}$ " roller bit to 41' using water
		R-1	NX	58%	NX DIAMOND CORE With water 41' to 45.5' 58% Recovery 13% = RQD Mortar seams @ 41.75' and 43.4'

DEPTH	CORE/SAMPLE	BLOWS PER FT.	SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO. SIZE	EXPT. CORE RQD RECVY		
45.5			<i>Rec</i> Voids - 42'-42.3' - 42.5'-42.7' - 42.8'-43.2'	
49.7	R-2	NX 69%	NX DIAMOND CORE from 45.5'-49.7' Voids - 45.8'-46.0' - 48.3'-48.4' - 49'-49.3'	Similar Rock 69% = Recovery 8% = RQD Mortar throughout run
56.2	R-3	NX 38%	NX DIAMOND CORE from 49.7' to 56.2' Voids - 50.3' - 50.4' 52.7' - 56.2' Advanced $3\frac{7}{8}$ " roller bit from 41' to 56.2' using "Clear Mud" drilling fluid	Grey Gneiss 38% Recovery 2% RQD
60'			END OF EXPLORATION 5-19-88 EXPLORATION CONTINUED 5-20-88 Advanced roller bit from 56.2' to 60' using "Clear Mud" drilling fluid	Granular Material
	S-9	2" 30%	23 22 Sampled from 60' to 62' using a 2" O.D. sampler advanced with a 140 lbs hammer	

(Test)

Boring No. FD 88-3

Hop Brook Dam, CT

FD88-3 (FD-C)

DEPTH		CORE/SAMPLE		BLOWS PER FT.		6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	1" 2"	NO	SIZE	DEPT. DOWN	CORE RECVY		
62'		S-9	2"	Rec 30%	21 28	Advanced roller bit to 70.3' using "clear mud" drilling fluid	Poorly graded sand with gravel (sp) About 60% brown sand with ≈ 35% cm ± gravel and < 5% fines (wet, rem- inable)
							Cobbles + coarse gravel
70.3'							Bedrock
		R-4	NX	100%		NX DIAMOND CORE From 70.3' to 75.3' Note: Drillers encountered difficult drilling i.e. hole was starting to collapse, therefore they could only obtain one 5' run of bedrock EXPLORATION TERMINATED 5/24/60	Grey gneiss 100% recovery 78% RQD
75.3'							

FIELD LOG OF TEST BORING IN ROCK

SITE Hop Brook Dam, CT

ROLE NO. FD 88-3 (FD-C)

PAGE 7

[illegible]

TOTAL BED ROCK DRILLED 20.2 FEET

TOTAL BED-ROCK RECOVERED 13 FEET

DRILLER M. Hawkins + P. McAloon

BFD ROCK RECOVERY 64 PERCENT

INSPECTOR Greg Hargrave

WED FORM 130
DEC 63

DISPATCH (1) OF APR 67 WHICH MAY BE USED UNTIL EXHAUSTED

CORPS OF ENGINEERS, U. S. ARMY
NEW ENGLAND DIVISION
FOUNDATION AND MATERIALS BRANCH
FIELD LOG OF TEST BORING

Site Hop Brook Dam CT PROJECT NO. D.O. 0006
 Hole No. FD88-4 Diam. (Casing) HW (4") Page 1 of Pages
 Co-ordinates: N FD - D E Boring Started May 23, 1988
 Drilled by Todd Burnham + Scott Fox Boring Completed May 24, 1988
 Report Submitted May 31, 1988

Purpose of Exploration To determine subsurface soil conditions and depth

Elevation Top of Hole 363.7 M.S.L. Casing Left in Place 0 Feet
 Total Overburden Drilled 32.7 Feet
 Elevation Top of Rock 331.0 M.S.L.
 Elevation Bottom of Hole 320.2 M.S.L.
 Total Rock Drilled 10 Feet
 Total Depth of Hole 43.5 Feet
 Core Recovered 93 %
 Core Recovered 9.3 Ft.; NX Diam. 2 1/2 In.
 Soil Samples 1 3/8 In. Diam. 10 No.
 Soil Samples In. Diam. No. Water Table Depth

Depth		Method of Drilling and Type of Bit Used	INDEX
From	To		
0.0	28	HW (4") spun casing	Ground Water <u> </u> Back of Page <u> </u>
28	33.5	3 3/8" roller bit with "Clear Mud"	Boring Location Sketch <u> </u> Back of Page <u> </u>
33.5	43.5	NX rock core	Overburden Record <u> </u> Page <u> </u>
0	30	split spoon soil sampling at 5' intervals	Rock Drilling <u> </u> Page <u> </u>
			<u> </u> Page <u> </u>
			<u> </u> Page <u> </u>
			<u> </u> Page <u> </u>

Prepared by Greg Hargrave Field Data
 Submitted by Atlantic Testing Laboratories, Ltd Lab. Data

U. S. ARMY
CORPS OF ENGINEERS
NEW ENGLAND DIVISION

Site Hop Brook Dam CT Page 1 of Pages

Boring No. FD 88-4 Desig. FD-D Diam. (Casing) HW (4")

FIELD LOG OF TEST BORING

Co-ordinates: N E

Elevation Top of Boring 363.7 M.S.L. Hammer Wt. 140 lbs Boring Started 5-23-88
Total Overburden Drilled 32.7 Feet Hammer Drop 30"
Elevation Top of Rock 331.0 M.S.L. Casing Left 0 Boring Completed 5-24-88
Total Rock Drilled 10 Feet | Subsurface Water Data | | Page
Elevation Bottom of Boring 320.2 M.S.L. | Obs. Well
Total Depth of Boring 43.5 Feet | Drilled By T. Ruchman + Scott Fox
Core Recovered 93 % No. Boxes 1 Mfg. Des. Drill CME 850
Core Recovered 9.3 Ft : NX Diam. 2 1/8 In. Inspected By: Greg Hargrave
Soil Samples 1 3/8 In. Diam. 10 No. Classification By: G. Hargrave
Soil Samples In. Diam. No. Classification By:

DEPTH	CORE/SAMPLE		BLOWS PER FT. CORE RECVY	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE			
2.0'	S-1A	2"	Rec 40%	6 5 7 7	Silty sand (SM) About 60% grey cmf sand, about 35% silt and \approx 5% fine gravel (moist, non-plastic)
3.0'	S-1B	2"			Silty sand (SM) About 50% brown cmf sand, about 45% silt and \approx 5% mf gravel (moist, non-plastic)
5.0'	S-2	2"	15%	10 3 3 3	Similar Soil (wet) (SM)
8.0'				Advanced casing to 8' cleaned casing to 8'	
10.0'	S-3	2"	30%	13 8 6 8	Similar Soil (SM)

GENERAL REMARKS:

Site Hop Brook Dam, CT					Boring No. FD 88-4 (FD-D1)		Page <u>3</u> of <u> </u>	
DEPTH 1:2'		CORE/SAMPLE		BLOWS PER FT. CORE RECOVERY	6" SAMPLING AND CORING OPERATIONS		CLASSIFICATION OF MATERIALS	
		NO.	SIZE	DEPTH FOOT				
				Rec				
13.0								
					8	Sampled from 13' to 15'		Similar Soil. (SM)
					6	Advanced casing to 18'		
		5-4	2"	40%	8	Cleaned casing to 18'		
15.0					10			
18.0								
					8	Sampled from 18.0' to 20.0'		Silty gravel with sand (GM) About 50% brown cmf gravel, 25% cmf sand and 25% silt (saturated, non-plastic)
					8	Advanced casing to 23'		
		5-5	2"	40%	27	Cleaned casing to 23'		
20.0					30			
23.0								
		5-6a			17	Sampled from 23' to 25'		Poorly graded sand (SP): about 95% brown cmf sand and < 5% silt (wet, non-plastic)
		5-6b	2"		38	Advanced casing to 28'		
		5-6c			72	Cleaned casing to 28'		
25.0					47			

DEPTH	CORE/SAMPLE		BLOWS PER FT.	6" SAMPLING AND CORING OPERATIONS	CLASSIFICATION OF MATERIALS
	NO.	SIZE			
28'			Rec		
				END OF EXPLORATION 5/23/88	
			100/3	EXPLORATION CONTINUED 5/24/88	
	5-7	2"	-	Sampled from 28' to 28.3'	Silty gravel with sand (GM) Around 60% mf gravel 25% cm f sand and 15% silt. (saturated, non-plastic)
30'			-	Advanced roller bit with "clear Mud" drilling fluid to 33.5'	
33.5'					Bedrock
			5"	NX DIAMOND CORE with water from 33.5' to 38.5'	Grey micaceous gneiss The entire run is weathered 96% Rec. 26% RQD
	R-1	NX			
38.5'			4"	NX DIAMOND CORE with water from 38.5' to 43.5'	Similar Rock Top 2' of run is weathered 90% Rec 34% RQD
	R-2	NX			
43.5'				EXPLORATION TERMINATED 5/24/88	

FIELD LOG OF TEST BORING IN ROCK

SITE Hop Brook Dam CT

SOLE NO. FD 88-4 (FD-D)

PAGE 5 of

DATE	DEPTH PT.		RUN PT.	RUN REC'V'Y PT.	REC'V'Y %	DRILLING BEHAVIOR			ACTUAL DRILLING TIME	BIT NO. SIZE AND TYPE	ADDITIONAL REMARKS
	FROM	TO				FEED	WATER	REASON FOR POLL			
5-24-88	33.5	38.5	5'	4.8'	96%	Medium	NO LOSS NOTED	5' run	27 min	NXM	Run 1
5-24-88	38.5	43.5	5'	4.5'	90%	Medium	NO LOSS NOTED	5' run	35 min	NXM	Run 2

TOTAL BED ROCK DRILLED 10 FEET

TOTAL BED-ROCK RECOVERED 9.3 FEET

BED ROCK RECOVERY 93 PERCENT

DRILLER Todd Burnham, Scott Fox

INSPECTOR Greg Hargrave

SECTION 9
OTHER RECORDS TAKEN

a. Survey Notes

①	STADIA DIST	VERT	ROD READ	
B-B	257°08'40" .97	89°45'40"	5.00	
B-D	75°39'40" 1.19	93°25'00"	5.00	
T.C.B-C HI=5.17				
BS-4460				
B-C	260°55'40" 5.20	91°14'	5.00	
B-A	271°37'40" 108°42'20" 3.32		5.00	
T.C.H.L.O HI=5.26				
BS 3457.8				

